



# University of the Philippines Visayas

Miag-ao, Iloilo, Philippines 5023

## SUPPLY AND PROPERTY SERVICES OFFICE

Contact No.: +639177077232

Website Address: www.upv.edu.ph

### REQUEST FOR QUOTATION

Date: March 19, 2024

Quotation Number: 2024 - 155

Mode of Procurement: SVP

MPS-2024 - 011m

Please quote us your best offer on the item/s listed below, subject to the terms and conditions.

- Submit proposal to SPSO City Campus or Miagao Campus or EMAIL to: pps@upv.edu.ph
- Indicate company name, address, and quotation number on the envelope or in your email subject.
- Affix full signature over printed name.

DEADLINE : 3.26.24

*Muzan*  
**EMILIZA C. LOZADA**  
 CHIEF, SPSO

Item No.	Qty	Unit	Item and Description	ABC	Offered Brand or Model	Unit Price / Total Price
1	2	unit	<p>(1.0 HP) Smart Inverter Wall Mounted/ Split type ACU, Cooling Capacity: 3.40 kW (max) or 11,600 (max) Btu./hr, 1-Phase/230V/60Hz, environmental-friendly refrigerant: R-32, coefficient of performance (COP): not less than 3.89 W/W, Rated Power consumption: not more than 1,200 W (max), Piping connections: gas; Ø9.5mm, liquid: Ø6.4mm, with Coanda panel's (air flow) at ceiling, wireless remote control with backlight and luminous button, Intelligent eye, Self-diagnosis function with digital display, auto restart after a power failure, All voltage guard-Super PCB (operating voltage range: 150V-264V, Protection range: 0-440V) NEMA 3R circuit breaker, electrical connection to existing ACU outlet, painted outdoor steel bracket, flushing and leak test of piping using nitrogen (250-450 psig), test using thermometer: minimum of 17 degrees should be the difference between supply and return air duct, including complete with installation testing and commissioning, Cleaning of unit: twice. Warranty: Five (5) years on the compressor, Three (3) years on PCBs and One (1) year on all parts, labor and other materials.</p> <ul style="list-style-type: none"> <li>• Indoor-outdoor distance: +15 ft. max.</li> <li>• Indoor/outdoor location: Ground Floor</li> <li>• Electrical supply: To lay-out from existing ACU lines/outlet</li> </ul> <p>(Suppliers are required to survey the location first before submitting their quotations-pls. coordinate with CDMO Electrical Section)</p>	55,000.00 / unit		
				ABC:		110,000.00

OUR / EARMARKED 2024-03-170-UGTL-OUR

#### Our Terms and Conditions

1. DELIVERY PERIOD: 20wd upon receipt of PO
2. PLACE OF DELIVERY: Storage Room-OUR, UPV Miagao Campus
3. PRICE VALIDITY: 30 days
4. Warranty Period: 1 yr on parts, labor, PCB, 5 yrs on compressor
5. PAYMENT TERMS: 30 days

P110K

After having carefully read and accepted your terms and conditions, I/We quote you on the item/s at prices noted above.

#### FAXED:

Date: \_\_\_\_\_ Time: \_\_\_\_\_

#### Personally Distributed:

#### Received by:

Signature over Printed Name

Date

Printed Name / Signature

Tel No. / Cellphone No. / E-mail Address

Date