



University of the Philippines Visayas

Miag-ao, Iloilo, Philippines 5023

SUPPLY AND PROPERTY SERVICES OFFICE

Contact No.: (033) 315-81-41/ +639177077232

Website Address: www.upv.edu.ph

REQUEST FOR QUOTATION

Date: April 25, 2024

Quotation Number: 2024 - 293

Mode of Procurement: SVP

MPS-2024 -016m

Please quote us your best offer on the item/s listed below, subject to the terms and conditions.

- Submit proposal to SPSO City Campus or Miagao Campus or EMAIL to: pps@upv.edu.ph
- Indicate company name, address, and quotation number on the envelope or in your email subject.
- Affix full signature over printed name.

DEADLINE : 5.2.24

M. Lozada
EMILIZA C. LOZADA
 CHIEF, SPSO

Item No.	Qty	Unit	Item and Description	ABC	Brand / Model	Total Price
1	1	unit	<p>2.5 HP, Inverter Wall Mounted/ Split type ACU, Min. Rated Cooling Capacity: 6.59 kW or 22,500 Btu/hr or higher, 1-Phase/230V/60Hz, environment-friendly refrigerant: R-32, coefficient of performance (COP): not less than 3.59 W/W or EER equivalent, CSPF should be equal or more than 6.30 Wh/Wh, Rated Power consumption: 1,835 Watts and not more than 2,300 Watts, Piping connections: gas: Ø12.7 mm, liquid: Ø6.4 mm, Drain: Ø16.0 mm, wireless remote control, Self-diagnosis function with remote controller, auto-restart after a power failure, 3D air flow (vertical and horizontal auto swing) All voltage guard – Super PCB (operating voltage range: 150V-264V or higher, Protection range: 0-440V or higher), NEMA 3R circuit breaker, electrical connection to existing ACU outlet, painted outdoor steel bracket and service area (min. 12 in.) flushing and leak test of piping using nitrogen (250-450 psig), test using thermometer: minimum of 17 degrees should be the difference between supply and return air duct, including complete with installation testing and commissioning. Cleaning of unit: Twice within a year. Pull-out of existing AC unit. Warranty: Five (5) years on the compressor, Three (3) years on PCBs and One (1) year on all parts, labor and other materials</p> <ul style="list-style-type: none"> • Indoor-outdoor distance: ±15 ft. • Indoor/outdoor location: Ground Floor • Electrical supply: To lay-out from existing ACU lines/outlet <p>(Suppliers are required to survey the location first before submitting their quotations - please coordinate with CDMO Electrical section)</p>	96,000.00		

SSF / EARMARKED 2024-04-295 SSF (REALIGNED FUNDS GF)

Our Terms and Conditions

1. DELIVERY PERIOD: 20wd upon receipt of PO
2. PLACE OF DELIVERY: SSF Office, UPV Miagao campus
3. PRICE VALIDITY : 30 days
4. Warranty Period : 5yrs on compressor, 3yrs on PCB, 1yr on parts & labor
5. PAYMENT TERMS : 30 days

₱96K

After having carefully read and accepted your terms and conditions, I/We quote you on the item/s at prices noted above.

FAXED:

Date: _____ Time: _____

Personally Distributed:

Received by:

Signature over Printed Name

Date

Printed Name / Signature

Tel No. / Cellphone No. / E-mail Address

Date