



# University of the Philippines Visayas

PROCUREMENT SECTION  
Miag-ao, Iloilo, Philippines 5023  
Tel/Fax: 033-3158141 / +63917-7077232  
EMAIL: pps@upv.edu.ph

## REQUEST FOR QUOTATION

Date: 2024-07-31  
Quotation Number: 2024-728  
Mode of Procurement: SVP  
MPS No. MPS-2024-039M

Please quote us your best offer on the item/s listed below, subject to the terms and conditions.

- Submit **sealed quotations** to SPSO Iloilo City or Miagao Campus or email to: [spso.upvisayas@up.edu.ph](mailto:spso.upvisayas@up.edu.ph)
- Indicate company name, address, and quotation number on the envelope or in your email subject.
- Affix full signature over printed name.

Please address to: EMILIZA C. LOZADA  
Chief, SPSO, UP Visayas  
Miagao, Iloilo

DEADLINE : 8.7.2024

*Emiliza C. Lozada*  
**EMILIZA C. LOZADA**  
CHIEF, SPSO

Item No.	Qty	Unit	Item and Description	ABC	Model Offer	Unit Price	Total Price
1	1.00	lot	<p><b>Purchase and Installation of One (1) Unit Air Conditioning Unit for UPV Little Theater</b></p> <p><b>4 Tonner. Inverter Floor Mounted Split type ACU</b>, Cooling Capacity: 15.50 kW or 52.900 (min) Btu/hr. 1- Phase 230V/60Hz, environment friendly refrigerant: R-32, coefficient of performance (COP): 2.45 W/W (min.), CSPF: 4.18 Wh/Wh. Power consumption (rated-cooling): 5.71 kW. Compressor Motor output: 2.40kW (max), Air flow rate (H/M/L): 1059/988/918 cfm. with Navigation remote controller/wireless remote controller, Coil type: Micro Channel. Compressor type. Hennetically sealed swing type. Piping connections: gas flare: 015.90 mm, liquid: 0 9.5 mm. Auto swing. 3 step switchable fan speed and auto, Self-diagnosis function, emergency operation, filter sign, auto restart, NEMA 3R circuit breaker, electrical connection to existing ACU outlet, outdoor steel bracket, including complete installation, testing and commissioning. Twice cleaning within a year supported w/report. <i>Warranty: 1 year on parts, PCB, labor, compressor and other materials.</i></p> <p>-Indoor-outdoor distance: -Indoor/outdoor location: Ground. Floor. +28 ft. -Electrical supply. To lay-out from existing ACU lines/outlet <b>(Suppliers are required to survey the location before submitting the quotation, please coordinate to CDMO)</b></p>	255,000.00			
<b>CDMO / EARMARKED 2024-07-733 GF UPV Reprog 1379th BOR (CDMO)</b>				<b>Total ABC - 255,000.00</b>			

### Our Terms and Conditions

1. DELIVERY PERIOD: 45 CALENDAR DAYS UPON RECEIPT OF NOA/NTP
2. PLACE OF DELIVERY: UPV- LITTLE THEATER IN UPV ILOILO CITY
3. PRICE VALIDITY : 30 DAYS
4. WARRANTY DATE: 1 YEAR ON PARTS, PCB, Labor, Compressor & other Materials
5. PAYMENT TERMS : 30 DAYS

After having carefully read and accepted your terms and conditions, I/We quote you on the item/s at prices noted above.

### FAXED:

Date: \_\_\_\_\_ Time: \_\_\_\_\_

### Personally Distributed:

Received by: \_\_\_\_\_  
Signature over Printed Name

\_\_\_\_\_ Date

\_\_\_\_\_  
Printed Name / Signature

\_\_\_\_\_  
Tel No. / Cellphone No. / E-mail Address

\_\_\_\_\_  
Date

**POSTED ON PHILGEPS**